

**ADDENDUM NO. 1  
TO  
CONTRACT DOCUMENTS, SPECIFICATIONS, AND ADVERTISEMENTS  
FIRE STATION #4 – PARKING LOT REHABILITATION  
PROJECT NO. CP340-911-1 (2024)**

TO: ALL PROSPECTIVE BIDDERS AND STAKEHOLDERS

DATE: March 22, 2024

---

This Addendum forms a part of the Contract Documents and Specifications and modifies the original documents as noted below. Acknowledge receipt of this Addendum in bid submittal in accordance with the bidding documents as directed on page 4. Failure to do so may subject a Bidder to disqualification.

This Addendum consists of (3) pages, which modifies the bid documents and bid pricing sheet.

---

Removal of Priming and Sanding of CSRB

Bidders are notified that priming and sanding, in accordance with GDOT Standard Specification 315, is to be removed from the project. Public Safety Staff will ensure hydration during curing by keeping surface damp with water truck.

Addition of Concrete Drop Inlet

Bidders are notified to add concrete drop inlet with iron grate at existing down-drain. Existing down-drain pipe may be reused. Complete costs associated with installation will be included in Item No 668.

Amended “Appendix D” Bid Pricing Sheet

Bidders are notified to use attached Bid Pricing Sheet, (Appendix D) which will replace pages 23 and 24 in the bid documents.

---

**THIS CONCLUDES ADDENDUM NO. 1 IN ITS ENTIRETY**

Bids not signed shall be declared as “Non-Responsive” and may not be considered for award.

**Appendix D  
BID PRICING**

**White County Project No.: CP340-911-1(2024)  
Fire Station No. 4 – 2024 Parking Lot Rehabilitation**

ITEM	ROADWAY	UNITS	QUANTITY	UNIT PRICE	DOLLAR AMOUNT
150-1000	TRAFFIC CONTROL	LS	1		
210-0100	GRADING COMPLETE	LS	1		
210-0250	UNDERCUT EXCAVATION OF UNSUITABLE SOLS FOR TRUCK APRONS OR OTHER AREAS, AS NEEDED	CY	350	\$7.50	
207-0203	FOUNDATION BACKFILL MAT., TP 2, FOR TRUCK APRONS	CY	152		
500	CLASS “D” CONCRETE, 4,000 PSI, INCLUDING DOWELS, REBAR, FORMING, FINISHING, COMPLETE IN PLANCE	CY	76		
315-1000	FULL DEPTH RECLAMATION WITH PORTLAND CEMENT, INCLUDING PULVERIZATION/RECYCLING OF EXISTING SOIL/CRUSHED STONE BASE AND EXISTING ASPHALT PAVEMENT MATERIALS. RECYCLE DEPTH TO BE 10 INCHES. RECONSTRUCTION TO INCLUDE HAULING, RESHAPING, GRADING, PROPER COMPACTION, AND CURING.	SY	2,432		
315	PORTLAND CEMENT TP. II 60 LBS/YD2 OF PORTLAND CEMENT	TN	75		
310-1101	GAB FOR BASE REPAIRS, AS NEEDED	TN	50		
402-3130	ASPH CONC 12.5 MM SUPERPAVE, GP 2, INCL BITUM MAT'L & H LIME/ 220 LBS per SY	TN	275		
413-1000	BITUM TACK COAT FOR ASPHALT TIE-INS TO EXISTING ASPHALT	GL	25		

652-2501	SOLID TRAFFIC STRIPE, 4 IN., WHITE, INCLUDING INSTALLING BUMP STOPS IN 4 PARKING SPACES	LS	1		
668	INSTALL DROP INLET WITH IRON GRATE, COMPLETE IN PLACE	LS	1		
	<b>TOTAL BASE BID</b>				

Bid submitted by: \_\_\_\_\_

Company Name

**NAME & TITLE OF PERSON AUTHORIZED TO SIGN**

\_\_\_\_\_  
Name (Print)

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Title